

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-10186-00-00  
Spot: NWNE Sec/Twnshp/Rge: 35-27S-20W  
4620 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: ZIMMERMAN D Well #: 1  
County: KIOWA Total Vertical Depth: 4977 feet

Operator License No.: 31980  
Op Name: LOTUS OPERATING COMPANY, L.L.C.  
Address: 914 E DOUGLAS  
WICHITA, KS 67202

PROD Size: 4.5 feet: 4968 WITH 150 SX CMT  
SURF Size: 8.625 feet: 350 WITH 300 SX CMT #1/ce1 75

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/12/2004 9:15 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: PUMP 25 SX CMT TO 4000' TO BREAK CIRCULATION. PLUG AT 750' WITH 30 SX CMT. PLUG AT 370' TO SURFACE.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/12/2004 10:00 AM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PUMP 25 SX CMT TO 4000' THROUGH TUBING TO BREAK CIRCULATION.  
MAXIMUM PRESSURE 1800 PSI. 1ST PLUG RAN TUBING TO 750'. WAS SOLID  
COULD NOT GET DOWN. SPOT 30 SX CMT. 2ND PLUG PULL TO 370'. CIRCULATE  
CMT TO SURFACE WITH 85 SX CMT. STAYED FULL.

Perfs:


| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4867 | 4876 |      |          |
| 4862 | 4866 |      |          |

RECEIVED  
MAR 22 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 850' OF 4 1/2" CASING.

Plugged through: TBG

District: 01



Signed: \_\_\_\_\_

(TECHNICIAN)

INVOICED  
DATE 3-22-04  
INV. NO. 2004061314

Form C-27