

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22550-00-00
Spot: SESEWNNE Sec/Twnshp/Rge: 31-16S-25W
4091 feet from S Section Line, 1360 feet from E Section Line
Lease Name: LEWIS-WILDGEN Well #: 5
County: NESS Total Vertical Depth: 4784 feet

Operator License No.: 33104
Op Name: ARIES OPERATING, LP
Address: 1221 MCKINNEY - SUITE 3100
HOUSTON, TX 77010

PROD Size: 5.5 feet: 4582 WITH 125 SX CMT
SURF Size: 8.625 feet: 1111 WITH 500 SX CMT

15548

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2004 9:45 AM
Plug Co. License No.: 4072 Plug Co. Name: PLAINS INC
Proposal Rcvd. from: BOB Company: ARIES OPERATING Phone: (713) 759-1981

Proposed Plugging Method: PLUG AT 2200' WITH 30 SX CMT & 100# HULLS. FREE POINT TUBING. SPOT 40 SX CMT AT 1300'.
PERFORATE AT 1100' & CIRCUALTE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/16/2004 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4540'. 1ST PLUG AT 2200' WITH 30 SX CMT & 100# HULLS. FREE POINTED TUBING THAT WAS STUCK IN HOLE & COULD ONLY GET 2200' OF TUBING. TUBING FROM 2200' TO 4500' WAS LEFT IN HOLE. 2ND PLUG SPOT 40 SX COMMON CMT WITH 3% CC AT 1300'. PULLED TUBING AND WAITED 1 HOUR. 3RD PLUG PERFORATED AT 1100' & PUMPED 250 SX CMT. CIRCULATED TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
4492	4505		
4431	4438		
4396	4416		

RECEIVED
MAR 22 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Michael Maier
(TECHNICIAN)

INVOICE

DATE 3-22-04
INV. NO. 2004061310

Form 0-273