

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-20677-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 22-11S-19W  
4950 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: VINE E Well #: 6  
County: ELLIS Total Vertical Depth: 3466 feet

Operator License No.: 7076  
Op Name: BLACK DIAMOND OIL, INC.  
Address: PO BOX 641  
HAYS, KS 67601

PROD Size: 5.5 feet: 3462 125 SX CMT  
SURF Size: 8.625 feet: 1228 575 SX CMT

#112<sup>65</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/16/2004 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed  
Plugging  
Method:

Ordered out 210 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/16/2004 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded casing back to 3010' - topped with 5 sxs cement using a dump bailer.  
Cut casing free at 2430'.  
Pulled up to 1600' - mixed and pumped 100 sxs cement with 300# hulls.  
Pulled up to 1230' - spotted 30 sxs cement with 100# hulls.  
Pulled up to 650' - spotted 30 sx cement.  
Pulled up to 250' - circulated cement with 40 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3373	3373		
3350	3350		
3327	3327		
3241	3241		
3198	3198		
3142	3142		
3062	3065		

RECEIVED  
MAR 22 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

*Jay Pfeifer*  
(TECHNICIAN)

INVOICED  
DATE 3-22-04

WV. NO. 2004061312

Form CP-2/3

MAR 17 2004

SKELLY OIL CO.

#6 VINE "E"

22-11-19W  
NW NW NE

DENVER, COLO.  
CONTR LEBEN DRILLING

CTY ELLIS

GEOL \_\_\_\_\_ FIELD SLOMON

E 1946 KB CM 10/26/70 CARD 11/25/70 IP P 56 B0 + 2 1/2 BW  
ARB 3462-70


SMP	TOPS	DEPTH	DATUM
15-051-20,677			
ANHY	1218	+ 728	
TOP	2924	- 978	
HEEB	3119	-1173	
LANS	3162	-1216	
ARB	3461	-1515	
ID	3466	-1520	

8 5/8" 1228/575SX; 5 1/2" 3462/125SX  
 DST(1) 2916-34(TOP)/90" REC 30' GIP  
 120' M DY W, BHP 772-732#/30" FP 39-6  
 DST(2) 3450-66 (ARB)/90" REC 40' OIL, 60'  
 SL OCM N/W, BHP 1087-1067#/30" FP 39  
 69#

CO TO 3466 TD SWB DN & BAIL 1 3/4BOPH  
 NAT O. BI 250 ACID SWB DN & SWB 12 BO N/  
 4HRS, DD 3467 FU 750 OYER NIGHT SWB 380  
 N/W/1HR, DD 3468 SWB 3 1/2BO/1HR, DD 3470  
 TD NO INC. 750 ACID SWB LD & SWB 85BL/2  
 HRS SWB 23 BO + 1 BW/5HRS AVG 4 1/2BFPH  
 LAST 2HRS 4% LD WTR POP & P 69 BOPD +  
 3BMPD & P 56 BO + 2 1/2 BW

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

NO LOG