



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-039-20166-06-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 30 1971 7-30-1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Russell Sullivan of Russ Casing Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Aylward Drilling Company,

Complete Address: 909 1st National Bank Building, Wichita, Kansas.

Lease Name: Huff Well No. B-1

Location: CNE-SE Sec. 9 Twp. 1 Rge. (E)(W)26

County: Decatur Total Depth 3565' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Sullivan was instructed to plug the well as follows:

289'--8 5/8" Surface casing, cement circulated with 225 Sx.  
3564'--5 1/2" Production casing cemented on bottom with 150 Sx. Well  
plugged back to 3559'. Top perforations from 3268' to 3271'.

Push plug to 3200', sand back to 3175' and set 5 Sx. cement with dump  
bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks  
gel and 135 Sx. cement, staged.

Very truly yours,

*H. L. Nichols*  
Conservation Division Agent