



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-039-20205-00-00

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1971

CONSERVATION DIVISION
Wichita, Kansas

3-23-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. August Trarbach of Sage Drilling, Co., Inc., has this date requested permission to plug the following described well:

Mr. Trarbach guarantees payment of the plugging fee.

Operator's full Name: Rosen Oil Corporation,

Complete Address: 200 Sutton Place, Wichita, Kansas.

Lease Name: Leonard Huff. Well No. 1

Location: CNW-NE Sec. 9 Twp. 1 Rge. (E)(W) 26

County: Decatur Total Depth 3600' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Trarbach was instructed to plug the well as follows:

268'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 900'.

Circulate hole with heavy mud. Pull DP to 1125' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent