

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

15-039-20074-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 26 1968
CONSERVATION DIVISION
Wichita, Kansas
11-26-1968

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Aylward Drilling Company,

Complete Address: 909 First National Bank Building, Wichita, Kansas.

Lease Name: Huff Well No. 1

Location: NE-NE-NW Sec. 10 Twp. 1 Rge. (E)(W) 26

County: Decatur Total Depth 3577 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

250'--7" OD Surface casing, cement circulated with 90 Sx.

Circulate hole with heavy mud. Pull DP to 1100' and displace 50 Sx.

cement thru DP. Pull DP to 260' and displace 15 Sx. cement thru DP.

Pull DP, set bridge @ 40' with $\frac{1}{2}$ sack hulls and 7 Sx. cement to bottom of cellar.

Very truly yours,

M. A. Nichols
Conservation Division Agent