

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
APR 22 1974
4-22-74
CONSERVATION DIVISION
Wichita, Kansas

15-039-20283-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Weber of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:Mr. Weber guarantees payment of the plugging fee.Operator's full Name: W. W. Sauvage, Incorporated,Complete Address: Oberlin, Kansas.Lease Name: Huff Well No. A-3Location: CNW-SE-NE Sec. 10 Twp. 1 Rge. (E)(W)26County: Decatur Total Depth 1636 Oil Well Gas Well Input Well SWD Well D & A Lost Hole XMr. Weber was instructed to plug the well as follows:214'--8 5/8" Surface casing, cement circulated with 140 Sx.
Top of Dakota section @ 925'. Lost circulation between 1623' & 1626',
unable to regain, elected to abandon hole.Push wooden plug to 1165', build rock bridge ontop of wooden plug with
1/4 yard crushed rock. Fill hole to surface with heavy mud, pull 1 joint
DP and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace
30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls
and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent