

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 P. O. Box 17027 3830 S. Meridian
 WICHITA, KANSAS 67217

15-039-20288-0000

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 11-27-1974
 NOV 27 1974

CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Kelso Casing Pulling has this date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: A. L. Abercrombie, Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Huff Well No. E-1

Location: CE/2-SE-NW Sec. 10 Twp. 1 Rge. (E) (W) 26

County: Decatur Total Depth 3595' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

241'--8 5/8" Surface casing, cement circulated.
3382'--4 1/2" casing cemented on bottom with 150 Sx. Well plugged back to
3358'. Top perforations from 3260' to 3267'.

Push plug to 3200', sand back to 3175' and set 3 Sx. cement with dump
bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks
gel and 150 Cu. Ft. cement, staged.

Very truly yours,

M. L. Nichols
 Conservation Division Agent