

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-21064-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 31-31S-7E
405 feet from N Section Line, 330 feet from W Section Line
Lease Name: GATTON Well #: 1
County: COWLEY Total Vertical Depth: 2500 feet

Operator License No.: 8653
Op Name: PETROLEUM TECHNOLOGIES, INC.
Address: 801 W. 47TH ST STE 412
KANSAS CITY, MO 64112

PROD Size: 4.5 feet: 2499 100 SX CMT ²⁵
SURF Size: 7 feet: 169 125 SX CMT #81

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/19/2004 12:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING
Proposal Rcvd. from: RICHARD D SINGLETON Company: BRADEN PETROLEUM & WELL PL Phone: (816) 392-4234

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2

MAR 16 2004

WICHITA, KS

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/19/2004 12:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sanded back 50' above perforations with 4 sacks of cement on top of sand. Shot and pulled casing to surface. Ran 1" tubing to 350' and circulated cement to surface with 92 sacks of 60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
2410	2420		

Remarks: BRADEN PETROLEUM & WELL PLUGGING DID CEMENTING

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

INVOICED
DATE 3-17-04
WEL. NO. 2004061298