

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-20155-00-00  
Spot: NWSW Sec/Twnshp/Rge: 12-28S-20W  
1980 feet from S Section Line, 810 feet from W Section Line  
Lease Name: RALSTIN C Well #: 1  
County: KIOWA Total Vertical Depth: 4892 feet

Operator License No.: 31980  
Op Name: LOTUS OPERATING COMPANY, L.L.C.  
Address: 914 E DOUGLAS  
WICHITA, KS 67202

PROD Size: 5.5 feet: 4892 WITH 75 SX CMT  
SURF Size: 8.625 feet: 614 WITH 375 SX CMT

1,5899

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/10/2004 3:15 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4800' WITH 5 SX CMT. PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - WIPER PLUG - 150# HULLS - 15 SX GEL.

Plugging Proposal Received By: STEVE MIDDLETON  
Date/Time Plugging Completed: 03/12/2004 2:30 PM

WitnessType: COMPLETE (100%)  
KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

03/10/04: SAND TO 4800' WITH 5 SX CMT. PUMP DOWN 8 5/8" WITH 300# HULLS. BLEW HOLE IN SURFACE CASING. 03/12/04: 1ST PLUG RAN TUBING TO 1250'. SPOT 15 SX GEL & 50 SX CMT. 2ND PLUG PULL TUBING TO 630' & SPOT 50 SX CMT. 3RD PLUG PULL TO 300' & SPOT 40 SX CMT. 4TH PLUG PULL TO 30' & SPOT 10 SX CMT. STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
4878	4886		

RECEIVED  
MAR 18 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2237' OF 5 1/2" CASING.

Plugged through: TBG

District: 01



Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED  
DATE 3-18-04  
INV. NO. 20040761304

Form CV-21