

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-21028-00-00  
Spot: NWNWNWNE Sec/Twnshp/Rge: 27-27S-19W  
5120 feet from S Section Line, 2520 feet from E Section Line  
Lease Name: BRENSING B Well #: 1  
County: KIOWA Total Vertical Depth: 668 feet

Operator License No.: 5118  
Op Name: TGT PETROLEUM CORPORATION  
Address: 7570 W 21ST ST N, STE1010D PO BOX  
WICHITA, KS 67275

PROD Size: 5.5 feet: 668 WITH 140 SX CMT  
SURF Size: 8.625 feet: 208 WITH 175 SX CMT

*#35<sup>00</sup>*

Well Type: SWD UIC Docket No: D23259.0 Date/Time to Plug: 03/12/2004 12:01 PM  
Plug Co. License No.: 5118 Plug Co. Name: TGT PETROLEUM CORPORATION  
Proposal Rcvd. from: HAROLD BELLRIVE Company: TGT PETROLEUM CORPORATION Phone: (316) 773-2266

Proposed Plugging Method: RIH W/TBG TO BOTTOM. PUMP 300# HULLS & 75 SX CMT. FILL TO TOP. POOH W/TBG, TOP 5 1/2" OFF WITH CMT. RU TO BACKSIDE & PUMP CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/12/2004 6:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PBTD 651'. 1ST PLUG RAN 2 3/8" TUBING TO 590'. MIX & PUMPED 150# HULLS & 95 SX CMT. TUBING PRESSURED TO 2500#. COULD NOT PULL. 2ND PLUG BACKED OFF TUBING @ 294'. RAN BACK IN HOLE & CIRCULATED CMT TO SURFACE WITH 33 SX CMT. TUBING WAS IN CMT @ 294'. HOLE FULL OF CMT.

Perfs:


Top	Bot	Thru	Comments
564	594		

RECEIVED  
MAR 18 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed Steve Durrant  
(TECHNICIAN)

INVOICED  
DATE 3-18-04  
INV. NO. 2004061306  
Form CP-2/3