

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20106-00-01
Spot: SENE Sec/Twnshp/Rge: 24-7S-31W
~~3370~~ 3440 feet from S Section Line, 660 feet from E Section Line
Lease Name: MCCORMICK Well #: 3
County: THOMAS Total Vertical Depth: ~~4253~~ feet 4248 ⁰⁶

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: PO BOX 2757 202 SOUTH ST. FRANCIS
WICHITA, KS 67201

PROD Size: 4.5 feet: 4245 w/150 sxs cmt
SURF Size: 8.625 feet: 282 w/200 sxs cmt

\$138⁰⁶

Well Type: EOR UIC Docket No: E26056.4 Date/Time to Plug: 03/10/2004 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: LARRY JACK Company: GORE OIL COMPANY Phone: (316) 263-3535

Proposed Ordered 500 sxs of Midcon II Cement and 500# hulls.
Plugging Plug through tubing.
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/10/2004 11:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface pipe set at 282' w/200 sxs cement.
4 1/2" production casing set at 4245' w/150 sxs cement.
8 5/8" surface pipe perforated at 1170' - circulated cement to surface.
Run tubing to 4030' - pumped 65 sxs cement with 400# hulls.
Pulled tubing to 2000' - pumped 75 sxs cement with 100# hulls - cement to surface.
Pulled tubing to surface - pumped 25 sxs cement.
Max. P.S.I. 500#. S.I.P. 400#.
Connected to 8 5/8" surface casing - pumped 5 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
4149	4159		

RECEIVED
MAR 17 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #6380.

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

INVOICED

DATE 3-18-04

INV. NO. 2004061302

Form CP-2/3

MAR 11 2004

DON E. PRATT
 P.O. BOX 370
 HAYS, KS.

24-7-31W
 140'NW, C SE NE

#3 MC CORMICK

CONTR MURFIN DRUG CO.

CTY THOMAS

GEOL GREEN & GREEN

FIELD REXFORD

E 2905 KB CW/3/77 CARD ISSUED 2/17/77 IP P 45 BOPD, NW
 LKC 4147-57

API 15-193-20, 106

LOG	TOPS	DEPTH	DATUM
ANH	2571	+	334
B ANH	2607	+	298
TOP	3744	-	839
HEEB	3935	-	1030
TOR	3962	-	1057
LKC	3977	-	1072
BKC	4215	-	1308
BTD	4255	-	1348

8-5/8" 282/200SX, 4 1/2" 4245/150SX
 DST (1) 4117-71 (LKC)/90", REC 650'
 GIP, 610'GSY 0, SIP 527#/30"-50" :/
 30", FP 98-276#
 MICT - CO, PF (LKC 'J1) 40/4147-57, SWB
 GSO & G, ON/FU 1400'FL NAT, 40'MDY FFL W
 ON BTM, SWB 12BOPH, AC 500, SWB 5BOPH,
 AC 3000CRA, SWB LD & SWB 14-3/4BOPH
 OFF BTM, POP.

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

MAOICEE