

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21239-00-00
Spot: SENW Sec/Twnshp/Rge: 35-27S-20W
3300 feet from S Section Line, 3300 feet from E Section Line
Lease Name: GEORGIA Well #: 1
County: KIOWA Total Vertical Depth: 4990 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 914 E DOUGLAS
WICHITA, KS 67202

PROD Size: 5.5 feet: 4990 WITH 175 SX CMT
SURF Size: 8.625 feet: 503 WITH 350 SX CMT

#10218

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/10/2004 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4750' & 5 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - WIPER PLUG - 150 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER
Date/Time Plugging Completed: 03/10/2004 1:45 PM

WitnessType: COMPLETE (100%)
KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 4950'. SAND TO 4750' WITH 5 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 150 SX CMT. MAXIMUM PRESSURE 350#. SHUT IN PRESSURE 100#.

Perfs:


Top	Bot	Thru	Comments
4892	4902		
4880	4886		
4813	4818		

RECEIVED
MAR 18 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3509' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed _____

(TECHNICIAN)

INVOICED

DATE 3-18-04

INVOICE NO. 2004061304

Form 2-23