

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01467-00-01

Spot: SENWSW

Sec/Twnshp/Rge: 1-9S-17W

1650 feet from S Section Line,

4290 feet from E Section Line

Lease Name: HRABE A

Well #: 2

County: ROOKS

Total Vertical Depth: 3439 feet

Operator License No.: 30606

PROD Size: 4.5 feet: 3439 w/200 sxs cmt

Op Name: MURFIN DRILLING CO., INC.

SURF Size: 8.625 feet: 166 w/150 sxs cmt

Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Well Type: EOR

UIC Docket No: E17200.2

Date/Time to Plug: 03/09/2004 9:00 AM

Plug Co. License No.: 30606

Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: JOHN GERSTNER

Company: MURFIN DRILLING CO., INC.

Phone: (316) 267-3241

Proposed Plugging Method: Squeezed 810' w/200 sxs cwc.
Squeezed 839' - 869' - 899' - 02-27-1986 w/200 sxs.
Top of tubing fish at 1054'.
Tubing and packer at 3099'.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/09/2004 11:30 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

M.I.R.U. company tools - ran 2" tubing to 892'.
Swift Services pumped 40 sxs Swift Multi-Density Cement - cement circulated.
PTOH. Swift pumped 35 sxs SMD neat, followed with 65 sxs with 200# hulls.
Max. P.S.I. 800#. S.I.P. 650#.
Hooked up to 8 5/8" braden head.
Swift pumped 18 sxs.
Max. P.S.I. 500#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3148	3366		

RECEIVED
MAR 15 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

3-17-04

INV. NO.

2004061292

Form CP-2/3

MAR 10 2004

1-9-17W
SE NW SW

MURFIN DR LG & R A COMEAU #2 HRABE A

Contr. MURFIN DR LG ROOKS County

E 2000 keComm. 8/11 Comp. 9/20/62 IP 32 BOPD + 12% WTR
LANS 3320-53, GR 38

Tops	Depth	Datum
ANHY	1278	+722
B/ANHY	1318	+682
JOP	2878	-878
HEEB	3097	-1097
TOR	3123	-1123
LANS	3143	-1143
B/KC	3366	-1366
TD	3439	-1439

Casing 8" 166 5" 3439
DST 3157-3216/1 HR, REC 240' MSW
BHP 630-190#; FP 0#
DST 3240-49/1 HR, REC 20' M, SSO
BHP 295-200# FP 0#
CO 3360: PERF 12/3350-53: ACID 1000
SWB 4 BOPH + 12% WTR, SET PKR PLUG
3340; PERF 12/3320-23: 16/3327-31
ACID 2000: SWB 6 BOPH/NW, NT, CO
3360 : SWB ALL ZND 10 BOPH + 12%
HRABE WEST

WTR/4 HRS POP
GEOL: BOB ARMSTRONG

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

MACLED