

KANSAS

E STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1971
CONSERVATION DIVISION
Wichita, Kansas

15-039-20205-00-00

3-23-1971

Operator's Full Name Rosen Oil Corporation,

Complete Address 200 Sutton Place, Wichita, Kansas.

Lease Name Leonard Huff Well No. 1

Location CNW-NE Sec. 9 Twp. 1 Rge. (E) (W) 26

County Decatur Total Depth 3600'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Building, Wichita, Kansas License No.

Operation Completed: Hour 6:00 AM Day 20 Month 3 Year 1971

The above well was plugged as follows:

268'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pull DP to 1125' and displace 100 Sx. cement thru
DP from 1125 @ 800'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. L. Nichols*
Well Plugging Supervisor

DATE 3/25/71
INV. NO. 3458-W