

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1974

CONSERVATION DIVISION
Wichita, Kansas

15-039-20283-00-00

H-22-1974

Operator's Full Name W. W. Sauvage, Incorporated.

Complete Address Oberlin, Kansas.

Lease Name Huff Well No. A-3

Location CNW-SE-NE Sec. 10 Twp. 1 Rge. (E) (W)26

County Decatur Total Depth 1636'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated "LOST HOLE", Lost circulation from 1623' to 1626',
was unable to regain. Elected to abandon hole.

Plugging Contractor Abercrombie Drilling, Incorporated,

Address 801 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 3:00 PM Day 16 Month 4 Year 1974

The above well was plugged as follows:

214'--7 5/8" Surface casing, cement circulated with 140 Sx.
Top of Dakota section @ 925'.

Pushed wooden plug to 1165', pulled DP and attempted to build rock bridge on top of
wooden plug with 1/4 yard chat. Hole bridged @ 600'. Circulated cement to surface
from 600' thru DP with 150 Cu. Ft. cement. (Cementing operations performed by Sun).

I hereby certify that the above well was plugged as herein stated.

Signed: R. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 4/23/74
INV. NO. 8971-W