

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
11-27-1974  
NOV 27 1974

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-039-20288-00-00

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name A. L. Abercrombie, Incorporated,

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name Huff Well No. E-1

Location GE/2-SE-NW Sec. 10 Twp. 1 Rge. (E) (W) 26

County Decatur Total Depth 3595'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling,

Address P. O. Box #176, Chase, Kansas. License No. 683

Operation Completed: Hour 11:00 AM Day 21 Month 11 Year 1974

The above well was plugged as follows:

241'--8 5/8" Surface casing, cement circulated.  
3382'--4 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 3358'. Top perforations from 3260' to 3267'.

Pushed plug to 3200', sanded back to 3175' and set 3 Sx. cement with dump bailer.

Pulled 4 1/2" casing (1121') and squeezed well initially with 2 sacks hulls and 13 sacks gel following with 110 Cu. Ft. cement from 1325' to 1000' then 18 sacks gel from 1000' to 280' and followed with 30 Cu. Ft. cement from 280' to 200' then 4 sacks gel from 200' to 40' and finally 10 Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in pressure-150#. FSIP-50#. (Mudding and cementing by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. D. Nichols  
Well Plugging Supervisor

INVOICED

DATE 12/2/74

INV. NO. 368-W