

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 30 1971 7-30-1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-039-20166-00-00

Operator's Full Name Aylward Drilling Company,
Complete Address 909 First National Bank Building, Wichita, Kansas.
Lease Name Muff Well No. B-1
Location CNE-SE Sec. 9 Twp. 1 Rge. (E) (W) 26
County Decatur Total Depth 3565'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Russ Casing Pulling, Incorporated,
Address Box #1082, Great Bend, Kansas. License No. 623
Operation Completed: Hour 1:00 PM Day 29 Month 7 Year 1971

The above well was plugged as follows:

289'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 900'.
3564'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to
3559'. Top perforations from 3268' to 3271'.
Pushed plug to 3200', sanded well back to 3175' and set 5 Sx. cement with dump bailer.
Pulled 5 1/2" casing (1605') and squeezed well initially with 5 sacks hulls and 13 sacks
gel and followed with 100 Sx. cement from 1125' to 800' then 12 sacks gel from 800' to
320' and followed with 25 Sx. cement from 320' to 240' then 5 sacks gel from 240' to
40' and finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in pressure-
150#. Final shut-in pressure--50#. (Mudding and cementing by Allied Cementing, Inc.).
I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 7-30-71

INV. NO. 4045-U