

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

*A*

WELL PLUGGING RECORD

15-137-00163-00-00

Norton 137 County, Sec 25 Twp 1S Rge. (2) 25 (W)

NORTH

#10		
	25	

Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines C NW NW  
Lease Owner British-American Oil Producing Co.  
Lease Name Yunt Well No. 1  
Office Address 501 Oil & Gas Bldg., Okla City, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed December 17 19 60  
Application for plugging filed December 17 19 60  
Application for plugging approved December 17 19 60  
Plugging commenced December 17 19 60  
Plugging completed December 17 19 60  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3658 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	215'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

First plug @ 400' w/20 sacks cement  
Second plug @ 200' w/20 sacks cement  
Top plug @ 40' w/10 sacks cement

STATE OF KANSAS  
01-13-1961  
JAN 13 1961  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E Drilling, Inc.  
Address 719 Union Center Bldg., Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Dale Silcott - employee of Contractor

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott  
719 Union Center Bldg., Wichita, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December, 19 60

My commission expires October 30, 1961

Wildalee Wind - Notary Public.



15-137-00163-00-00  
**DRILLER'S WELL LOG**

OPERATOR: BRITISH-AMERICAN OIL PRODUCING COMPANY  
 501 Oil and Gas Bldg.  
 Oklahoma City, Oklahoma

WELL NAME: #1 Yunt  
 LOCATION: C NW NW  
 Section 25-1S-25W  
 Norton County, Kansas

CONTRACTOR: **K & E DRILLING, INC.**  
 719 UNION CENTER BLDG.  
 WICHITA, KANSAS

COMMENCED: December 9, 1960

CASING RECORD: 8 5/8" @ 215' w/150 sx

COMPLETED: December 17, 1960

ELEVATION:

ROTARY TOTAL DEPTH: 3658'

PRODUCTION: Dry hole

**FORMATION RECORD**

*Depths shown indicate bottom of formations encountered.*

Soil and clay	60
Sand	90
Clay	140
Shale	850
Sand and shale	975
Sand and shale-pyrite	1698
Shale and sand	1910
Anhydrite	1940
Shale and sand	2075
Shale	2750
Shale and lime	3010
Lime	3168
Lime and shale	3260
Shale	3352
Shale and lime	3455
Lime	3480
Shale and lime	3560
Lime and shale	3636
Granite wash	3658

STATE OF KANSAS  
 JAN 17 1961  
 CONSTRUCTION DIVISION  
 Wichita, Kansas

**CERTIFICATION**

State of KANSAS }  
 County of SEDGWICK } ss:

I, Dale Silcott of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

*Dale Silcott*  
 Dale Silcott

Subscribed and sworn to before me this 29th day of December, 1960.

*Wildalee Wind*  
 Wildalee Wind - Notary Public.

My Commission expires: October 30, 1961.

