


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Decatur

County. Sec. 8 Twp. 1S Rge. 26 (X) (W)

Location as "NE/CNW/SW" or footage from lines. C SE SE

Lease Owner Barron Kidd

Lease Name Huff Well No. 1

Office Address 3707 Rawlins, 405 Oak Plaza Bldg., Dallas, Texas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-26 19 64

Application for plugging filed 8-26 19 64

Application for plugging approved 8-26 19 64

Plugging commenced 8-26 19 64

Plugging completed 8-26 19 64

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols, State Pluggger

Producing formation Depth to top Bottom Total Depth of Well 3530 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug set @ 600' with 20 sacks  
2nd plug set @ 180' with 30 sacks  
3rd plug set @ 40' with 10 sacks

RECEIVED  
STATE CORPORATION COMMISSION  
9-2-1964  
SEP 2 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor (not contractor) Burch Exploration, Ltd. plugged this well  
Address 1011 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK  
Earl M. Burch, contractor

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl M. Burch

1011 Union Center (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of September, 19 64

My commission expires June 18, 1968

Minnie E. Matson  
Minnie E. Matson Notary Public.

CONTRACTOR'S  
WELL LOG

15-039-00206-00-00

Barron Kidd #1 Huff  
C SE SE Sec. 8-1S-26W  
Decatur County, Kansas

Set 8-5/8" surface casing @ 170' with 200 sacks.  
Commenced: 8-19-64  
Completed: 8-25-64  
Elevation: 2407 KB

D & A

170 Sand  
1433 Shale & Sand  
1780 Shale & Lime & Sand  
1875 Shale & Red Bed  
1904 Anhydrite  
3490 Lime & Shale  
3525 Granite Wash  
3530 Granite  
  
3530 Rotary Total Depth

Tops  
Severy 3001 (-594)  
Topeka 3036 (-629)  
Oread 3127 (-720)  
Lansing 3186 (-779)  
B Zone 3225 (-818)  
Base Kansas City 3395 (-988)  
Cherokee Sand 3465 (-1058)  
Granite Wash 3490 (-1083)  
Granite 3520 (-1113)

DST #1. 3180-3195. Open 1 hr. 20 mins. Shut  
in 30 mins. Recovered 8' mud. IBHP 1165#;  
IFP 20#; FFP 20W; FBHP 1160#.


DST #2. 3216-3247. Open 1 hr. shut in 30  
mins. Recovered 1' oil and 6' mud. IBHP 693#;  
IFP 39#; FFP 9#; FBHP 33#.

STATE OF KANSAS )  
 ) ss:  
COUNTY OF SEDGWICK )

RECEIVED  
STATE CORPORATION COMMISSION  
9-3-1964  
SEP 3 1964

CONSERVATION DIVISION  
Wichita, Kansas

I, Earl M. Burch, General Partner of Burch Exploration, Ltd. being duly  
sworn on oath, state: That I have knowledge of the facts, statements and  
matters herein contained and that the same are true and correct.



Earl M. Burch, General Partner

Subscribed and sworn to before me this 1st day of September, 1964.



Minnie E. Matson, Notary Public

My commission expires: June 18, 1968