

10-21

4-031604

87  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-039-20332-00-00

C NE NE /4 SEC. 10, 01 S, 26 W  
4620 feet from S section line  
660 feet from E section line

Operator license# 6962

Lease Huff well # A-4

Operator: W.W. Sauvage, Inc.

County Decatur

Address: Box 132  
Oberlin, Kansas 67749

Well total depth 3590 feet <sup>116.67</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 223 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton License# -

Address: Oberlin, Kansas 67749

Company to plug at: Hour: P.M. Day: 21 Month: October Year: 91

Plugging proposal received from: Herb Seaman

Company: Sauvage, Inc. Phone:

Were: 8 5/8" set @ 223' w/160 sx. cwc. 4 1/2" set @ 3540' w/150 sx.  
P.B.T.D. 3540'. Perf's. 3440' - 46' / 3296' - 3306'. Hole sanded in to  
1750' with fish @ 1750'. Milled on fish. No recovery. Order 200 sx.  
65/35 poz. - 10% gel. - 500# hulls. Halliburton Cement Company.  
LaRue Water Trucks. Poe Rig.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 3:50P.M. Day: 21 Month: October Year: 91

Actual plugging report: Ran tubing to 1750' circulated cement blend  
to surface. Squeezed 4 1/2" with total of 350 sx. cement blend with  
500# hulls mixed in to max. P.S.I. 500#. Close in P.S.I. 200#.  
Cement circulated on the backside. Closed in 8 5/8" squeezed with  
5 1/2. Plug complete.

Remarks:

RECEIVED  
STATE CORPORATION COMMISSION  
11-18-1991  
NOV 18 1991  
CONSERVATION DIVISION  
Wichita, Kansas

I did  / did not  observe the plugging.

Carl Goodrow

**INVOICED**

DATE 11-22-91

John S.

(agent)

INV. NO. 33840

Form CP-2/3