

4-032143

15-039-20494-00-01

213
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

3-14

API Number: 15- - 1981

E2 SE SE /4 SEC. 09 , 01 , 26 W
660 feet from S section line
330 feet from E section line

Operator license# 8294

Lease: Huff Well # 1

Operator: C. Dale Stromquist

County: Decatur

Address: P.O. Box 1054
Liberal, Kansas 67905-1054

Well total depth 3630 117.97 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 289 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage License# 31529

Address: Chase, Kansas 67525

Company to plug at: Hour: A.M. Day: 14 Month: March Year: 1996

Plugging proposal received from: Richard

Company: Mike's Testing & Salvage Phone:

Were: Order 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cementing Company.
Order sand and common cement.
This is an area of lost circulation when holes were drilled.

RECEIVED
KANSAS CORPORATION COMMISSION
4-8-1996
APR 08 1996

CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:15 A.M., Day: 14, Month: March, Year: 1996

Actual plugging report: 8 5/8" set at 289' cwc with 225 sxs. 4 1/2" set at 3622' with 200 sxs. Prod. Perfs. - 3281' - 3412'. Sand back to 3200' with 4 sxs common cement on sand with bailer. Shots at 1900' and 1100'. Mixed and pumped down 4 1/2" casing - 50 sxs cement blend with 400# hulls. Displace to 1900' with water. Shots at 800' and 400'. Mixed and pumped to circulate with 75 sxs cement blend. Pulled 4 1/2" casing - cement at surface. Used total 125 sxs cement blend with 400# hulls. Plug complete.

Remarks:
Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow

(agent)

Form CP-2/3

100

INVOICED
DATE APR 11 1996
INV. NO. 45194