

4-032142 15-039-20532-00-00P ²¹³

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

3-27

API Number: 15- - 1980

C NE SE /4 SEC. 09 , 01 , 26 W
560 feet from N section line
560 feet from E section line

Operator license# 8294

Lease: Huff - Twin Well # 2

Operator: C. Dale Stromquist

County: Decatur

Address: P.O. Box 1054
Liberal, Kansas 67905-1054

Well total depth 3625 ^{117.81} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 248 feet

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Mike's Testing & Salvage License# 31529

Address: Chase, Kansas 67525

Company to plug at: Hour: P.M. Day: 27 Month: March Year: 1996

Plugging proposal received from: Richard

Company: Mike's Testing & Salvage Phone: _____

Were: Order 200 sxs 60/40 pozmix - 10% gel - 400# hulls.
Allied Cementing Company.
Order sand and common cement.

RECEIVED
KANSAS CORPORATION COMMISSION
APR 08 1996
4-8-1996
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 12:00 P.M. , Day: 27 , Month: March , Year: 1996

Actual plugging report: 8 5/8" set at 248' cwc with 250 sxs. 4 1/2" set at 3622' with 200 sxs. Prod. Perfs. - 3264' - 3343'. PBT 3502'. Sand back to 3260' with 4 sxs common cement on sand with bailer. Shots at 1900' and 1100'. Mixed and pumped down 4 1/2" casing - 100 sxs cement blend with 400# hulls. Shots at 714' and 330'. Mixed and pumped 100 sxs cement blend to circulate. Pulled 330' of casing - cement fell. Topped off with 20 sxs cement blend. Used total 220 sxs cement blend with 500# hulls. Plug complete.

Remarks: _____

Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES _____ NO _____
Bottom plug(in place): YES _____, CALC _____, NO _____ Dakota plug: YES _____, NO _____
Plugged through TUBING _____, CASING _____ Elevation: _____ GL

I did[] / did not[] observe the plugging.

Carl Goodrow
(agent)

INVOICED

PO-

Form CP-2/3

DATE APR 11 1996

INV. NO. 45193