

6 031408

API NUMBER 15- 039-20,564-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NE, SEC. 9, T 1 S, R 26 W/E

3300 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6962

Lease Name Huff Well # C 1

Operator: W. W. Sauvage Inc.

County Decatur 116.54

Name & Address Box 132

Well Total Depth 3586 feet

Oberlin, ks. 67749

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well xx Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Oberlin, Ks.

Company to plug at: Hour: AM Day: 30 Month: August Year: 19 90

Plugging proposal received from Herb Seeman

(company name) Sauvage Inc. (phone)

were: 8 5/8 set at 249 w/250 sks. cwc 4 1/2 set at 3586 w/200 sks. perfs 3263-3348.

Petro Jet shots at 1150 and 2000. Order 300 sks 65/35 poz 10% gel 500 lbs. hulls.

Halliburton Cement Co. LaRue Water Trucks.

Pulled rods and tubing.. Hole open to production perfs.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part None

Operations Completed: Hour: 10:45AM Day: 30 Month: August Year: 19 90

ACTUAL PLUGGING REPORT Sq 4 1/2 w/250 sks cement blend w/450 lbs. hulls

mixed into max psi 300 lbs. Close in psi 150 lbs. Sq 8 5/8 w/50 sks cement blend w/50 lbs

hulls mixed into max psi 200 lbs. Close in psi 200 lbs. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
10-3-1990
OCT 3 1990

Remarks: Additional description is necessary, use BACK of this form.)

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE 10-5-90

INV. NO. 29551

Gibbs

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow