

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-039-20532-  
00-00

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE NAME Huff  
 WELL NUMBER 2  
 \_\_\_\_\_ Ft. from S Section Line  
 \_\_\_\_\_ Ft. from E Section Line  
 SEC. 9 TWP. 1 RGE. 26 (E) or (W)

LEASE OPERATOR C. Dale Stromquist  
 ADDRESS P.O. Box 1054 Liberal, Ks. 67905  
 PHONE#(316) 624-3902 OPERATORS LICENSE NO. 8294

COUNTY Decatur  
 Date Well Completed 10-30-80  
 Spud:  
 Plugging Commenced 3-13-96  
 Plugging Completed 3-28-96

Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)  
 The plugging proposal was approved on \_\_\_\_\_ (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 3630'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	248	none
				4 1/2"	3622	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section.  
Plugged off bottom with sand to 3260', dumped 4 sacks cement. Shot pipe at 1900', and 1150' pumped 100 sacks cement with 100# bulls displaced to 800'. Shot pipe at 714', and 330' pumped 100 sacks cement, pulled casing. Topped off 8 5/8" casing with 20 sacks cement. (60/40 POZMIX 10% gel) Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529  
 Address P.O. Box 209 Chase, Kansas 67524

RECEIVED  
 KANSAS CORPORATION COMMISSION  
4-8-1996  
APR 08 1996  
 CONSERVATION DIVISION  
 WICHITA, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: C. Dale Stromquist - Liberal, Ks.  
 STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances of the above-described well as filed to the State of Kansas, and matters herein contained and the log of the above-described well as filed to the State of Kansas are true and correct, so help me God.

(Signature) [Signature]  
 (Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 2nd day of April, 19 96

[Signature]  
 Notary Public

My Commission Expires: \_\_\_\_\_

