

15-039-20283-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:

Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Decatur County. Sec. 10 Twp. 1S Rge. (E) 26 (W)

Location as "NE/CNWxSWx" or footage from lines C NW SE NE

Lease Owner W. W. Sauvage, Inc.

Lease Name Huff "A" Well No. 3

Office Address P. O. Box 132, Oberlin, Kansas 67749

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 16 1974

Application for plugging filed (verbally) April 16 1974

Application for plugging approved (verbally) April 16 1974

Plugging commenced April 16 1974

Plugging completed April 16 1974

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols

Producing formation Depth to top Bottom Total Depth of Well 1636' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7 5/8"	222'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set rock bridge at 600' with 1/4 yd. chat; cement to surface with 100 sx. 50/50 posmix. Job completed 12:00 noon 4-16-74.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 22 1974  
CONSERVATION DIVISION  
Wichita, Kansas

4-22-1974

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.  
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of April, 1974

Beverly Mann  
Beverly Mann - Notary Public.

CONTRACTOR'S WELL LOG

15-039-20283-00-00

OPERATOR: W. W. Sauvage, Inc.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: HUFF "A" #3  
 LOCATION: C NW SE NE, Sec. 10-1S-26W  
 Decatur County, Kansas  
 GEOLOGIST: Jack K. Wharton  
 SPUD DATE: April 9, 1974  
 COMPLETION DATE: April 16, 1974

0	116	Clay & Sand
116	121	Flint
121	150	Sand and Rock
150	1135	Shale
1135	1280	Sand
1280	1623	Shale
1623	1636	Sand
	1636	Rotary Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 22 1974  
 4-22-1974  
 CONSERVATION DIVISION  
 Wichita, Kansas

Drilled 223' of 9-7/8" hole, set 7-5/8" casing at 222' K.B. w/140 sacks  
 Sunset cement. Cement circulated. Plug down at 4:00 p.m., April 9, 1974.  
 Set rock bridge at 600'. Filled hole with cement to surface, with 100 sx.  
 50/50 posmix. Job completed 12:00 noon April 16, 1974.

STATE OF KANSAS        )  
                                   ) SS  
 COUNTY OF SEDGWICK    )

Jerry A. Langrehr, Vice President of Abercrombie Drilling, Inc., does hereby  
 state that the above and foregoing is a true and correct copy of the log of  
 the HUFF "A" #3, C NW SE NE, Section 10-1S-26W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr  
 Jerry A. Langrehr  
 Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid  
 county and state as of this 18th day of April, 1974.

Beverly Mann  
 Beverly Mann, Notary Public

My Commission Expires:  
 February 10, 1975