

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
67202 TYPE OR PRINT

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-039-20565
LEASE NAME HUFF B Wichita, KS

WELL NUMBER 4

NOTICE: Fill out completely 4620 Ft. from S Section Line
and return to Cons. Div. 4620 Ft. from E Section Line
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 10 TWP. 1S RGE. 26W (E) or (W)
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY DECATUR
PHONE # (316) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 3/31/81

Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 3/26/03
Plugging Completed 3/31/03

The plugging proposal was approved on 3/31/03 (date)
by Darrel Dipman w/KCC Hays, KS. (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? no
Producing Formation LKC Depth to Top 3256 Bottom 3344OA TD 3590 Show
depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	251	8 5/8	251	0
	RECEIVED	production	3546	4 1/2	3546	0
	APR 17 2003					

Describe in detail the mud placed in the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

KCC WICHITA
Plugged well as follows: TIH w/tbg. To 935'. Top of parted tbg @982. Pumped 50 sxs SMD cmt & 60 sxs SMD cmt w/400# hulls & circ cmt to surface. TOH w/ tbg. Hooked up to 8 5/8" csg. Pumped 10 sxs & press to 200# & held. Hooked up to 4 1/2' csg. Pumped 20 sxs & press to 200# and held. Well P/A. Witnessed and approved by Darrel Dipman w/ KCC Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address
250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK .ss.
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Tom W. Nichols
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 1st day of April 2003

Notary Public - Barbara J. Dodson

My Commission Expires: 12/16/09 Form CP-4 Revised 05-88

