

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20552-00-00
Spot: CNWNWSE Sec/Twnshp/Rge: 1-1S-26W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: OHARE Well Number: 2
County: DECATUR Total Vertical Depth: 3576 feet

Operator License No.: 8981
Op Name: ADECO, INC.
Address: BOX 873
HAYS, KS 67601

Conductor Pipe: Size feet: 3116.22
Surface Casing: Size 8.625 feet: 248 w/185 sxs cmt
Production: Size 4.5 feet: 3574 w/200 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/07/2002 12:30 PM
Plug Co. License No.: 8981 Plug Co. Name: ADECO, INC.
Proposal Rcvd. from: WALLY WALHMEIER Company: ADECO, INC. Phone: (785) 625-6010

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
4 1/2" set at 3574' w/200 sxs.
No squeeze records.
Perforate anhydrite at 1950' and Dakota at 1266'.
F.L. 2000' from surface.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/07/2002 2:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated one shot at 1950' anhydrite and one shot at 1266' base of Dakota.
Allied pumped 215 sxs 60/40 pozmix - 10% gel with 400# hulls down 4 1/2" casing.
Max. P.S.I. 100#. S.I.P. 100#.
Pumped 35 sxs with 100# hulls down backside.
Max. P.S.I. 100#. S.I.P. 50#.

RECEIVED
MAR 11 2002
3-11-02
KCC WICHITA

Remarks:

Plugged through: CSG

District: 04

MD

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE Mar 12-02

INV. NO. 2002061517

MAR 08 2002