



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-039-20260-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 23 1973  
03-23-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Weber of Abercrombie Drilling, Inc., has this  
date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Helm Well No. 1

Location: CNE-SE Sec. 2 Twp. 1 Rge. (E)(W) 26

County: Decatur Total Depth 3627' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Weber was instructed to plug the well as follows:

203'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 850'.

Circulate hole with heavy mud. Pull DP to 1075' and displace 110 Cu. Ft.  
cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

M. L. Nichols  
Conservation Division Agent