



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-039-20279-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1973
11-27-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Weber of Abercrombie Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Helm Well No. B-1

Location: CSW-NW Sec. 2 Twp. 1 Rge. (E)(W) 26

County: Decatur Total Depth 3610' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Weber was instructed to plug the well as follows:

205'--10 3/4" Surface casing, cement circulated with 125 Sx. (9" Hole).
Top of Dakota section @ 1350'.

Circulate hole with heavy mud. Pull DP to 1575' and displace 150 Cu. Ft. cement thru DP. Pull DP to 215' and displace 35 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 15 Cu. Ft. cement to bottom of Cella.

Very truly yours,

N. J. D. [Signature]
Conservation Division Agent