

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-039-20279-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 27 1973  
11-27-1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Abercrombie Drilling, Incorporated.  
Complete Address 801 Union Center Building, Wichita, Kansas.  
Lease Name Helm Well No. B-1  
Location CSW-NW Sec. 2 Twp. 1 Rge. (E) (W) 26  
County Decatur Total Depth 3610'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated       
Plugging Contractor Above  
Address      License No.     

Operation Completed: Hour 7:00 PM Day 22 Month 11 Year 1973

The above well was plugged as follows:

205'--10 3/4" Surface casing, cement circulated with 125 Sx.  
Top of Dakota section @ 1350'.

Circulated hole with heavy mud. Pulled DP to 1575' and displaced 150 Cu. Ft. cement  
thru DP from 1575' to 1250'. Pulled DP to 215' and displaced 35 Cu. Ft. cement thru  
DP from 215' to 155'. Pulled DP, set bridge @ 40' with 1 sack hulls and 15 Cu. Ft.  
cement to bottom of cellar.

**INVOICED**

I hereby certify that the above well was plugged as herein stated.

DATE 11/29/73

INV. NO. 8208-W

Signed: M. L. Dechuk  
Well Plugging Supervisor