

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1973
03-23-1973
CONSERVATION DIVISION
Wichita, Kansas

15-039-20260-00-00

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name Helm Well No. 1

Location CNE-SE Sec. 2 Twp. 1 Rge. (E) (W) 26

County Decatur Total Depth 3627'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 12:45 PM Day 20 Month 3 Year 1973

The above well was plugged as follows:

203'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @850'.

Circulated hole with heavy mud. Pulled DP to 1075' and displaced 110 Cu. Ft. cement
thru DP from 1075' to 750'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu.
Ft. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *H. L. Dickel*
Well Plugging Supervisor

INVOICED

DATE 3-23-73

INV. NO. 7168-W