

STATE OF KANSAS
STATE CORPORATION COMMISSION


15-039-20260-00-00

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Flat

Decatur County, Sec. 2 Twp. 1S Rge. (X) 26 (W)
Location as "NE/CNWSW" or footage from lines C - NE - SE
Lease Owner Abercrombie Drilling, Inc.
Lease Name Helm Well No. 1
Office Address 801 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 20, 1973
Application for plugging filed (verbally) March 20, 1973
Application for plugging approved (verbally) March 20, 1973
Plugging commenced March 20, 1973
Plugging completed March 20, 1973
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols, Morland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3627 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRGM	TD	SIZE	PUT IN	PULLED OUT
				8-5/8	208	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug set at 1075' w/110 sx. cement
2nd plug set at 215' w/30 sx. cement
3rd plug set at 40' w/10 sx. cement

Plugging completed 12:45 p.m. 3-20-73

State Plugger - Bill Nichols

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1973
03-23-1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of March, 1973

My commission expires February 10, 1975

Beverly Mann
Beverly Mann
Notary Public.

CONTRACTOR'S WELL LOG

15-039-20260-00-00

OFFICER:
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: HELM #1
 LOCATION: C NE SE Sec. 2-1S-26W
 Decatur County, Kansas
 GEOLOGIST: Jack K. Wharton
 SPUD DATE: March 15, 1973
 COMPLETION DATE: March 20, 1973

0	175	Clay, Flint & Sand
175	213	Shale
213	850	Shale & Shells
850	915	Sand
915	1665	Shale & Sand Streaks
1665	1958	Sand
1958	1988	Anhydrite
1988	2475	Shale
2475	2674	Shale & Lime
2674	3225	Lime & Shale
3225	3627	Lime
	3627	Rotary Total Depth

Drilled 213' of 12 1/2" surface hole. Set 8-5/8" sfs. csg. at 210' K.B. w/155 sx. Sunset cement. Plug down at 10:30 p.m. 3-14-73. D & A.

ELECTRIC LOG TOPS

Anhydrite	1964 (# 519)
Heebner	3259 (- 786)
Lansing	3294 (- 821)
B/K.C.	3523 (-1050)
Lawson Sand	3562 (-1089)
Granite Wash	3609 (-1136)
ELTD	3628 (-1155)

ELEVATION:

2473 K.B.
 2472 D.F.
 2466 G.L.

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 23 1973
 03-23-1973
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Helm #1, C NE SE, Sec. 2-1S-26W, Decatur County, Kansas.

Abercrombie Drilling, Inc.

By Jerry A. Langrehr
 Jerry A. Langrehr
 Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 22nd day of March, 1973.

Beverly Mann
 Beverly Mann, Notary Public

My commission expires:
 February 10, 1975