

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-039-20, 701
00-00

LEASE NAME Helm

WELL NUMBER 1-2

SPOT LOCATION NW NE NE

SEC. 2 TWP. 1S RGE. 26 (or 27)

COUNTY Decatur

Date Well Completed 9/8/83

Plugging Commenced 8/9/84

Plugging Completed 8/9/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR ADVANTAGE RESOURCES, INC.

ADDRESS 1600 Broadway #1940 Denver, Co. 80202

PHONE #(303) 831-1912 OPERATORS LICENSE NO. 6926

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, KS

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation Lansing Depth to top 3293 bottom 3526 T.D. 3622
Cherokee 3572

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Cherokee	Oil	3578	81	4 1/2	3621	
Lansing B	Oil	3342				
Lansing A	Oil	3298				
Lansing F	Oil	3483	85			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. #1-1 Helm - Mixed 2 sacks Hulls with gel plus 50 sacks, 50/50 Pozmix cement 6% gel, 2% CACL4. Pumped in at 800 P.S.I., Mixed and pumped in 10 sacks gel at 600 P.S.I. Mixed 95 sacks, 50/50 Pozmix cement, shut in at 1400 P.S.I. Mixed 50 sacks, 50/50 Pozmix cement and pumped down Annulus.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____
Address Box 47 Oberlin, Kansas 67749

STATE OF Kansas COUNTY OF Decatur, ss.

John Zimmerman (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) John Zimmerman
(Address) 1600 Broadway #1940 Denver, CO 80202

SUBSCRIBED AND SWORN TO before me this 8th day of Oct., 1984

My Commission expires: April 30, 1988

Michelle L. Barton
Notary Public