

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-04970-00-00
Spot: SWSESW Sec/Twnshp/Rge: 24-11S-18W
330 feet from S Section Line, 3630 feet from E Section Line
Lease Name: MARSHALL E Well #: 9
County: ELLIS Total Vertical Depth: 3530 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 SOUTH MARKET STREET
WICHITA, KS 67202

PROD Size: 5.5 feet: 3530 150 SX CMT
SURF Size: 8.625 feet: 1197 525 SX CMT

#114 73

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/18/2004 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/18/2004 2:45 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 5 1/2" - mixed and pumped 150 sxs cement with 400# hulls.
Displaced to 1800'.
Pulled casing free at 2010'.
Pulled up to 1200' - spotted 50 sxs with 200# hulls.
Pulled up to 650' - spotted 30 sxs cement with 100# hulls.
Pulled up to 250' - circulated cement with 70 sxs.
POOH. Topped with 10 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3501	3503		

RECEIVED
MAR 23 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

Jay Pfeifer
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 3-23-04

INV. NO. 2004061322

MAR 19 2004