

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25250-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 33-15S-17W  
4950 feet from S Section Line, 4490 feet from E Section Line  
Lease Name: SCHLEGEL Well #: 1-33  
County: ELLIS Total Vertical Depth: 3606 feet

Operator License No.: 5214  
Op Name: LARIO OIL & GAS COMPANY  
Address: 301 SOUTH MARKET STREET  
WICHITA, KS 67202

COND Size: 13.38 feet: 90  
PROD Size: 5.5 feet: 3604 140 SX CMT  
SURF Size: 8.625 feet: 1040 450 SX CMT

\$117<sup>20</sup>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/11/2004 10:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: BRAD SANDER Company: LARIO OIL & GAS COMPANY Phone: (785) 625-5023

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/11/2004 12:45 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Sanded to 3425' with 5 sxs cement.  
Cut off casing at 2650'.  
Pulled to 1700'.  
Pumped 110 sxs 60/40 pozmix - 10% gel cement with 300# hulls.  
Pulled to 1030'.  
Pumped 40 sxs cement with 200# hulls.  
Pulled to 300' and circulated with 60 sxs cement.  
POOH.

Perfs:

Top	Bot	Thru	Comments
3498	3504		
3488	3494		

RECEIVED  
MAR 23 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

*CM*

Signed \_\_\_\_\_

*Case Morris*

(TECHNICIAN)

INVOICED

DATE

3-23-04

INV. NO

200406/322

MAR 19 2004