

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-21112-00-00  
Spot: S2SWSE Sec/Twnshp/Rge: 7-13S-21W  
660 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: MORTON Well #: 1  
County: TREGO Total Vertical Depth: 4050 feet

Operator License No.: 33069  
Op Name: ENCORE OPERATING COMPANY  
Address: 1601 BLAKE STREET, SUITE 500  
DENVER, CO 80202

PROD Size: 5.5 feet: 4027 175 SX CMT  
SURF Size: 8.625 feet: 244 175 SX CMT

# 131<sup>23</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/17/2004 12:30 PM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: ROLAND NYP Company: ENCORE OPERATING COMPANY Phone: (785) 737-3242

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/17/2004 1:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Annulus full of cement.  
Swaged onto 5 1/2" - mixed and pumped 240 sxs cement with 500# hulls.  
Max. P.S.I. 500#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3888	3930		

RECEIVED  
MAR 23 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 3.23.04  
INV. NO. 2004061321

MAR 19 2004

INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS


REPLACEMENT CARD

TRIPLE "H" OIL OPERATIONS  
P. O. BOX 248 #1 MORTON 7-13-21W  
HAYS, KS 67601 C S/2 SW SE

CONTR DREILING OIL, INC. CTY TREGO

GEOL JOHN CARNES FIELD RIGA NW

ELV 2207 K.B. SPD 11/10/82 CARD ISSUED 4/21/83 IP P 67 BOPD, NW  
2202 GL MARM 3888-3930 0A



LOG	Tops	Depth Datum	
ANH	.....	1636+	571
TOP	.....	3293-	1086
HEEB	.....	3523-	1316
TOR	.....	3542-	1335
LANS	.....	3557-	1350
BKC	.....	3800-	1593
MARM	.....	3885-	1678
ARB	.....	4016-	1809
LTD	.....	4049-	1842
RTD	.....	4050-	1843

API 15-195-21,112  
8 5/8 " 244 / 175SX, 5 1/2 " 4027 / 175SX  
DST (1) 3605-3663 (LANS) / 30-45-60-30, REC 60' M, SIP 800-679#, FP 47-56 / 56-56#, BHT 90°  
DST (2) 3894-3923 (MARM) / 30-60-30-60, 528' GIP, REC 961' CL GSY OIL, 124' MCO, SIP 652-652#, FP 130-279 / 279-373#, BHT 100°  
MICT - CO, PF (MARM) 3888-3930, W/1 SPF, AC 4000G (15% MCA) & 1000 BBL FR WTR FRAC, SWB LD, GSO, SET 2 3/8 " TBG (DEPTH NA), POP, P 67 BOPD, NW, 7/27/83

INFO RELEASED: 7/12/84 - WAS OIL WELL - TIGHT HOLE