

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-01566-00-01  
Spot: NWSE Sec/Twnshp/Rge: 1-11S-16W  
1980 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: BOWLBY OWWO Well #: 3  
County: ELLIS Total Vertical Depth: 3520 feet

Operator License No.: 31824  
Op Name: BROWN, THOMAS M.  
Address: 403 NW 3RD PO BOX 250  
PLAINVILLE, KS 67663

PROD Size: 4.5 feet: 3420 w/175 sxs cmt  
SURF Size: 8.625 feet: 150 w/100 sxs cmt

*11440*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/19/2004 11:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: THOMAS M. BROWN Company: BROWN, THOMAS M. Phone: (785) 434-7141

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Squeezed 10-28-1968 at 728' w/150 sxs cwc thru branden head.  
PBTD 3379'. Fluid Level 2900'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/19/2004 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 350 sxs 60/40 pozmix - 10% gel with 500# hulls.  
Max. P.S.I. 200#. S.I.P. 0#.  
Hooked up to backside and pumped 50 sxs cement.  
Max. P.S.I. 500#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3128	3133		

RECEIVED  
MAR 23 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

*170-*

Signed

*Richard Williams*

(TECHNICIAN)

INVOICED

DATE 3-23-04

REV. NO. 2004061320

Form CP-2/3


MAR 22 2004

DATE

TIME

# IMAGICEP

2-182 Map No. OWWO  
 OPER BIRMINGHAM-BARTLETT DRLG. CO.  
300 KAUFMAN BLDG. WICHITA, KS.  
 WELL #3 BOWLBY  
 CONTR CO. TOOLS  
 FIELD BOWLBY (LAN OIL)  
 I.P. STATE POT: P 52 BOPD (GR 41DEG) & 20% WTR,  
LAN 3128-33 - COMPLETED 2-21-66



S-T-R 1-11S-16W  
 SPOT C NW SE  
 CO ELLIS, KS.  
 ELEV 1913 KB

(KB LOG)

TOP	2808 - 895
HB	3049 -1136
TOR	3071 -1158
LAN	3099 -1186
BKC	3348 -1435
CGL SD	3444 -1531
CGL SD	3465 -1552
ARB	3503 -1590
LTD	3520 -1607

OLD INFO; (WAS RAINS & WILLIAMSON OIL CO.)  
 SPUD 3-4-63 8" 150 W/100 SX.- B. LOUNSBURY WAS GEOL  
 DST #1 (TOP) 2832-2869, OP 1 HRS, R 10' O SPK M, ISIP  
 952#/30", FP'S 11-11#, FSIP 578#/30"  
 DST #2 (LAN) 3048-3110, OP 1 HRS, R 410' GCM & 600' GC  
 & OCSW (10% OIL-EST), ISIP 1334#/30", FP'S 157-488#,  
 FSIP. 1160#/30"  
 DST #3 (LAN) 3118-35, OP 1 HRS, R 270' OGCM & 120' MCSW,  
 ISIP 594#/30", FP'S 62-172#, FSIP 574#/30"  
 DST #4 (LAN) 3162-3205, OP 1.HRS, R 420' MCSW, ISIP 543#/  
 30", FP'S 60-236#, FSIP 354#/30"  
 DST #5 (LAN) 3298-3350, OP 1 HR, R 30' SOCM, ISIP 991#/  
 30", FP'S 15-27#, FSIP 78#/30", RTD 3520, D&A 3-14-63  
 NEW INFO:  
 MIRT 1-11-66  
 NO DST'S, CO 3420, 4" 3420 W/175 SX.  
 PF 20/3128-33 (LAN), NTN, 750A, § LD, § 2 BOPH &

(KB SPL)

ANH	1091 + 821
TOP	2809
TOR	2972
LAN	3094
BKC	3348
ARB	3503
RTD	3520

*States Inc*