

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22283-00-01
Spot: NWSWSW Sec/Twnshp/Rge: 17-7S-17W
990 feet from S Section Line, 4950 feet from E Section Line
Lease Name: LOOK Well #: 1
County: ROOKS Total Vertical Depth: 3325 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

PROD Size: 5.5 feet: 3322 140 SX CMT
SURF Size: 8.625 feet: 1191 350 SX CMT

#108^{ok}

Well Type: SWD UIC Docket No: D23507.0 Date/Time to Plug: 03/17/2004 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 150 sxs 60/40 pozmix - 10% gel - 400# hulls.
SWD permitted under Docket D-23,507.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/17/2004 4:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3275' and topped with 5 sxs cement using a dump bailer.
Cut casing off at 2220'.
Pulled up to 1250' - mixed and spotted 75 sxs cement with 300# hulls.
Pulled up to 550' - spotted 30 sxs cement with 100# hulls.
Pulled up to 200' - circulated cement with 45 sxs.

Perfs:

Top	Bot	Thru	Comments
3324	3368		

RECEIVED
MAR 23 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Jay Pfeifer
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 3-23-04

TEL NO 2004061319

MAR 19 2004

17-7-17W
 NW SW SW
 #1 LOCK
 ROCKS
 RIFFE EXT (1/8 E)

JAY C. BOYER
 P. O. BOX 511
 HAYS, KS 67601

CONTR PIONEER DRILLING CO. CTY ROCKS

GEOL _____ FIELD RIFFE EXT (1/8 E)

ELV 1753 KB SPD 2/3/84 CARD ISSUED 11/1/84 IP P 3 BO & 15 BWPD

API 15-163-22,283 SHAW 2716-2720
 LKC 2943-3102 OA
 ARB 3291-3310 OA

+	+	+
+	+	+
+	+	+

LOG	Tops	Depth/Datum
ANH	1194+	559
*B/ ANH	1223+	530
TOP	2687-	934
HEEB	2897-	1144
TOR	2922-	1169
LANS	2940-	1187
BKC	3170-	1417
ARB	3282-	1529
RTD	3324-	1571
LTD	3325-	1572
* SAMPLE TOP		

8 5/8 " 1191/350SX, 5 1/2 " 3322/140SX
 NO DST'S
 MICT - CO, PF (ARB) 9/ 3306-10, SWB DWN, SO, PF (ARB) 9/
 3291-95, AC 250G (INS), SWB DWN, SO, PF (LKC) 9/ 3100-02, 9/
 3038-42, AC 1500G (15% DEM), SWB DWN, SO, RE-AC (3038-
 42), W/ 2000G (15% DEM), SWB DWN, SO, PF (LKC) 1/ 2981, 1/
 2943, AC 1000G (15% DEM), SWB DWN, SO, RE-AC 1000G (15%
 DEM), SWB DWN, SO, PF (TOP) 2716-20, W/ 2 SPF, AC 500G
 (15% DEM), SWB DWN, SO, POP, P 3 BO & 15 BWPD, 6/28/84 -
 COMMINGLED

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS