

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22293-00-01  
Spot: NWNESE Sec/Twnshp/Rge: 1-11S-16W  
2310 feet from S Section Line, 990 feet from E Section Line  
Lease Name: BOWLBY A Well #: 5  
County: ELLIS Total Vertical Depth: 3560 feet

Operator License No.: 31824  
Op Name: BROWN, THOMAS M.  
Address: 403 NW 3RD PO BOX 250  
PLAINVILLE, KS 67663

PROD Size: 5.5 feet: 3559 w/210 sxs cmt  
SURF Size: 8.625 feet: 322 w/225 sxs cmt

*\$ 115<sup>20</sup>*

Well Type: EOR UIC Docket No: E21979.1 Date/Time to Plug: 03/19/2004 10:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: THOMAS M. BROWN Company: BROWN, THOMAS M. Phone: (785) 434-7141

Proposed Plugging Method: Ordered out 340 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Squeezed 1118'-1120' in May 1983; 634'-635' in May 1983.  
PBSD 3520'. Fluid Level 2000'+.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/19/2004 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 250 sxs 60/40 pozmix - 10% gel with 500# hulls.  
Max. P.S.I. 600#. S.I.P. 500#.  
Hooked up to backside and pumped 20 sxs cement.  
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3140	3227		

RECEIVED  
MAR 23 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams

(TECHNICIAN)

INVOICED

DATE 3-23-04

INV. NO. 2004061320

Form CP-2/3

MAR 22 2004

PHILLIPS PETROLEUM COMPANY  
P.O. BOX 287  
GREAT BEND, KS. 67530

REPLACEMENT CARD

1-11-16W  
NW NE SE

PHILLIPS PETROLEUM COMPANY  
P.O. BOX 287  
GREAT BEND, KS. 67530

#5 BOWLBY 'A'

CONTR SLAWSON DRILLING

CTY ELLIS

GEOL

FIELD BOWLBY

+	+
+	+
+	+
+	+

ELV 1939 KB SPD 10/31/81 CARD ISSUED 1/5/82 IP P 12.5 BO & 34 BWPD  
1933 GL LKC 3140-3227 OA  
API 15-051-22,293

SMP	Tops	Depth/Datum	
TOP	2838-	899	8 5/8 " 322 / 225SX, 5 1/2 " 3559 / 210SX NO DST'S RPTD
HEEB	3080-	1141	MICT - CO, PF (LKC) 3148-3149, W / 2 SPF, SWB DWN, NS, SQZD PFS W / 50SX, CO CMT, PF (LKC) 3140-3144, 3156-3160 & 3224-3227, W / 2 SPF, AC 1500G (XW-39), SWB DWN, SO, POP, P 12.5 BO & 34 BWPD (GR 36°), 11/21/81
TOR	3101-	1162	
LANS	3130-	1191	
CONG	3478-	1539	
ARB	3504-	1565	
RTD	3560-	1621	

NOTE: 1/2/86 - RE-ISSUED CARD - MAY BE MISSING FROM SOME FILES