

4-041998

15-14700747-00 01

E-08,461

12-16

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-14700747-0000

SW SE NW /4 SEC. 32, 01 S, 18 W
2970 feet from S section line
3630 feet from E section line

Operator license# 5242

Lease: Dixon Well # 1

Operator: Petroleum Management, Inc.

County: Phillips 114.47

Address: 14201 East Central
Wichita, Kansas 67230

Well total depth 3522 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 189 Feet
W/130 sxs.cmt.

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 15 Month: December Year 1998

Plugging proposal received from: Jason Bach - Leland Bach

Company: Petroleum Management, Inc. Phone: 316-733-5600

Were: 5 1/2" casing set at 3250' w/250 sxs cement.

Ordered 325 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Perfs at 3401' - 3481'.

Perf casing at 1820' and 1275'. Junk in the hole.

RECEIVED
STATE CORPORATION COMMISSION
Wichita, Kansas
DEC 28 1998
15-147-00747-0000

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 10:15 A.M. Day: 16, Month: December Year: 1998

Actual plugging report: R.I.H. with tubing to 1850'. Spotted 150 sxs cement with 400# hulls mixed in cement. Pulled tubing to 900' and pumped 80 sxs cement with 300# hulls, shut down overnight. R.I.H. with tubing. Tagged T.O.C. at 1100'. Pumped 80 sxs cement with 300# hulls. Circulated at surface. P.O.O.H. with tubing and squeezed casing with 10 sxs cement to Max. P.S.I. 200#.

8 5/8" S.P. Squeezed 25 sxs cement with 100# hulls. Max. P.S.I. 200#.

Remarks:

Condition of casing(in hole): GOOD BAD X Any plug: YES X NO

Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO

Plugged through TUBING X CASING Elevation: G.L.

I did[X] / did not[] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

DEC 29 1998

60494