

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-20074-00-00  
Spot: CNWSW Sec/Twnshp/Rge: 32-1S-18W  
1980 feet from S Section Line, 4620 feet from E Section Line  
Lease/Unit Name: HUFFSTUTTER E Well Number: 5  
County: PHILLIPS Total Vertical Depth: 3588 feet

Operator License No.: 31569  
Op Name: BACH OIL PRODUCTION  
Address: RR 1, BOX 28  
PHILLIPSBURG, KS 67661

Conductor Pipe: Size feet:  
Surface Casing: Size 8.62 feet: 203 145 SX CMT  
Production: Size 4.5 feet: 3626 250 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/17/2001 8:00 AM

Plug Co. License No.: 31569 Plug Co. Name: BACH OIL PRODUCTION

Proposal Rcvd. from: JASON BACH Company: BACH OIL PRODUCTION Phone: (785) 542-5615

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Wireline TD 3673'. Top of fluid at 800'+.  
Casing squeezed at 1226' to 2385' with 640 sxs.

Plugging Proposal Received By: DENNIS HAMEL  
Date/Time Plugging Completed: 04/17/2001 9:45 AM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: DENNIS HAMEL

**Actual Plugging Report:**

R.U. Cementers to 8 5/8" S.P.  
Squeezed 30 sxs cement with 50# hulls mixed in cement.  
R.U. Cementers to 4 1/2" casing.  
Squeezed 170 sxs cement with 450# hulls mixed in cement.  
Max. P.S.I. 1000#. S.I.P. 350#.

**INVOICED**  
DATE 5-7-01  
INV. NO. 2001061767

**RECEIVED**  
KANSAS CORPORATION COMMISSION  
MAY 7 2001  
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY

Plugged through:

District: 04

Signed Dennis L. Hamel  
(TECHNICIAN)

*ND*

APR 23 2001

PETROLEUM MANAGEMENT, INC. #5 HUFFSTUTTER 'E' C NW SW 32-1-18W  
WICHITA, KS.

Contr. RED TIGER DRLG. CO. City. PHILLIPS

Geol. BILL PETERSEN Pool HUFFSTUTTER

E. 2202 KB Cm. 6/21/69 Cp. 10/30/69 IP EST 25 BOPD, NW/  
LANS 3422-3480

API 15-147-20,074


SMPTops	Depth	Datum
ANH	1765	+ 437
B ANH	1787	+ 415
HEEB	3339	-1137
TOR	3368	-1166
LANS	3384	-1182
BKC	3607	-1405
RTD	3627	-1425

Csg. 8-5/8" 203/145 SX  
4 1/2" 3626/250 SX  
DST 3447-3495/60", 3'M, BHP  
223-95#/45", FP 21-23#  
SWB DN, PF 3422-26, 3440-44  
3458-60, 3464-66, 3476-80  
4500 ACID, SWB LD, POP

NO LOG  
NO CORES

PETERSEN

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS