

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-00744-00-00  
Spot: NENESW Sec/Twnshp/Rge: 32-1S-18W  
2310 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: HUFFSTUTTER E Well Number: 7  
County: PHILLIPS Total Vertical Depth: 3517 feet

Operator License No.: 31569  
Op Name: BACH OIL PRODUCTION  
Address: RR 1, BOX 28  
PHILLIPSBURG, KS 67661

Conductor Pipe: Size feet:  
Surface Casing: Size 8.62 feet: 183 125 SX CMT  
Production: Size 5.5 feet: 3517 150 SX CMT  
Liner: Size feet: 114.30

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/17/2001 9:00 AM

Plug Co. License No.: 31569 Plug Co. Name: BACH OIL PRODUCTION

Proposal Rcvd. from: JASON BACH Company: BACH OIL PRODUCTION Phone: (785) 543-5615

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Wireline measure - 3518'. Top of fluid at 800'+.  
Hole in casing at 1100'.

Plugging Proposal Received By: DENNIS HAMEL

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 04/17/2001 11:15 AM

KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Rigged up cementers to 8 5/8" S.P.  
Squeezed down annulus with 50 sxs cement with 50# hulls mixed in cement.  
Max. P.S.I. 300#. S.I.P. 150#.  
Rigged up cementers to 5 1/2" casing.  
Squeezed down casing with 275 sxs cement with 450# hulls mixed in cement.  
Max. P.S.I. 350#. S.I.P. 200#.

INVOICED  
DATE 5-7-01  
INV. NO. 2001061767

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 7 2001  
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through:

District: 04

Signed Dennis L Hamel  
(TECHNICIAN)

APR 23 2001

B & R DRILLING, INC. # 7 HUFFSTUTTER E NE NE SW 32-1-18W 6


Contr. \_\_\_\_\_ PHILLIPS County

E. 2234 Comm. \_\_\_\_\_ Comp. 11-2-51 IP 80 BOPD  
PHY. POT

Tops	Depth	Datum
HEEB	3376	=1142
LANS	3403	=1169
T.D.	3517	=1283

Casing  
8" 189 PERF 24 S 3456-64  
5" 3517 ACID 3000  
SWB 2 BOPH

HUFFSTUTTER POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

HUFFSTUTTER POOL  
 11-2-51  
 80 BOPD  
 PHY. POT