

6070257

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-137-20, 348-00-00

SE-SE, SEC. 20, T. 1 S, R 23 0/E

600 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8301

Lease Name RICHARD L. WYATT Well # 1620

Operator: ADVANCED RESOURCES
Name & Address STOEPPELWERTH DRIG. INC.

County NORTON 117.98

BOX 978
MC COOK, NEBRASKA
69001

Well Total Depth 3630 feet

Conductor Pipe: Size 0 feet V

Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated TAG # 1449

Plugging Contractor STOEPPELWERTH DRIG. INC License Number 8301

Address BOX 978 - MC COOK, NEBRASKA - 69001

Company to plug at: Hour: 10:00 AM Day: 19th Month: NOV Year: 19 84

Plugging proposal received from LONNIE MALLICK

(company name) STOEPPELWERTH DRIG. INC (phone) 308-345-1766

were: 8 5/8" - 253 FT SQ. CUL. #1/225 5X 60/40 Permiox 3% CA-CL (BY HALLIDAYTON)

ORDER 200 5X 50/50 Permiox 6% 3% CA-CL - 1 5X 710 CELL - AND 8 5/8" PING.

SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PINGS

(NO ARBUCKLE -) ELV. 2407 - ANH 1924 - NO CIRCULATION PROBLEMS

MUD WEIGHT 9.0 - VISCOSITY 45.

Plugging Proposal Received by [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:00 AM Day: 19th Month: NOV Year: 19 84

ACTUAL PLUGGING REPORT ORDERED 200 5X 50/50 Permiox 6% 3% CA-CL - 1 5X 710 CELL - 8 5/8" PING.

SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PINGS

1st PING @ 1940 FT #1/30 5X CNT 2nd PING @ 1260 FT #1/100 5X CNT 1 Cell

3rd PING @ 270 FT #1/50 5X CNT, 4th PING SOLID BRIDGE @

40 FT to 0 #1/10 5X CNT, 10 5X IN RAT HOLE (CON)

Permented by Hallidayton CNT

STATE CORPORATION COMMISSION
11-26-84
NOV 26 1984

Remarks: _____ (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-28-84

INV. NO. 4954

11-19

JAN 14 1985

Signed [Signature] (TECHNICIAN) 11-26-84

BOIC

FORM CP-2/3
Rev. 01-84

CARD, MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 11 12 84
month day year ~~20~~ 350

API Number 15- 137-20,348-00-00

OPERATOR: License # 8301
Name Stoepfelwerth Drilling Inc., &
Address Box 978 Advanced Resources
City/State/Zip McCook, NB 69001
Contact Person Jack Lowry
Phone 308 345 1766

SE SE Sec .. 20 Twp .. 1 S, Rge .. 23. East
(location) West

..... 600 Ft North from Southeast Corner of Section
..... 660 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 8301
Name .. Stoepfelwerth Drilling, Inc.
City/State ... same as above

Nearest lease or unit boundary line 660 feet.
County Norton
Lease Name Richard L. Wyatt Well# 16-20

Well Drilled For: Well Class: Type Equipment:
 Oil Swd XXX Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Domestic well within 330 feet : yes no
Municipal well within one mile : yes no

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 3700 feet
Projected Formation at TD
Expected Producing Formations

Depth to Bottom of fresh water 150 feet
Lowest usable water formation Dakota
Depth to Bottom of usable water ~~200~~ 1200 feet
Surface pipe by Alternate : 1 2 XX
Surface pipe to be set 230 feet
Conductor pipe if any required feet
Ground surface elevation feet MSL

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

This Authorization Expires 5-9-85
Approved By 11-9-84 R

ite 11-9-84. Signature of Operator or Agent *Raquel Robles* Title As. Agent.....

Form C-1 4/84

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1984

CONSERVATION DIVISION
Wichita, Kansas