

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 13 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Tilco, et al. 15-137-20032-00-00

Complete Address 200 Sutton Place, Wichita, Kansas.

Lease Name Rhoades Well No. 1

Location NE-NW-SE Sec. 35 Twp. 1 Rge. (E) (W) 24

County Norton Total Depth 3631'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Leben Drilling, Incorporated,

Address Box #486, Great Bend, Kansas. License No.       

Operation Completed: Hour 9:00 AM Day 7 Month 8 Year 1969

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 850'.

Circulated hole with heavy mud. Pulled DP to 1075' and displaced 100 Sx. cement  
thru DP from 1075' to 750'. Pulled DP to 240' and displaced 20 Sx. cement thru DP  
from 240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement  
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/13/69

INV. NO. 288-W

Signed: W. L. Nichole  
Well Plugging Supervisor