

6 030383

API NUMBER 15-137-20,353-00-00
SWNESW SEC. 19, T. 1 S, R. 22 (W) E
1650 feet from #(S) section line
3630 feet from #(E) section line

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9703
Operator: BING Producing Co.
Name & Address 705 S. Elgin Ave.
P.O. Box 2115
Tulsa, Oklahoma 74101-2115

Lease Name Donovan Well # 1-19
County Norton 123.11
Well Total Depth 3788 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 256'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilg. License Number 5302 ^{Reg.} 96
Address Wichita Kansas

Company to plug at: Hour: P.M. Day: 17 Month: 2 Year: 19 85

Plugging proposal received from mike
(company name) Red Tiger (phone) _____

were: 8 5/8 set @ 256' w/ 185sf. Hole Circulated w/ 50+Vis. mud.
Ordered 190sf 50/50 6% Papel 3% cc. + 2sf Flo Seal. 8 5/8" wiper Plug.

Halliburton Cement Co.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 7:10PM Day: 17 Month: 2 Year: 19 85

ACTUAL PLUGGING REPORT With hole full of heavy mud. Spot with 4 1/2" drill
pipe. 25sf Cement @ 2015' - 100sf Cement @ 1300' - 40sf @ 300' - 5BP. 8 5/8"
Hulls and 10sf @ 40'. Circulate rathole with 15sf cement.

Elev. 2447 KB Only 2002-2030 arb-3700

FEB 25 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Water From Farm Pond - Logged.
(If additional description is necessary, use BACK of this form.)

INVOLVED

I (did / did not) observe this plugging.

DATE 2-26-85

Signed Carl Goodrow
(TECHNICIAN)

2,22-85
28

INV. NO. 7131

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: February 1 1985
month day year

API Number 15- 137-20,353-00-00

OPERATOR: License # 9703
Name CNG Producing Company
Address 705 S. Elgin Ave., P.O. Box 2115
City/State/Zip Tulsa, Oklahoma 74101-2115
Contact Person Greg Bechtol
Phone 918-599-4005

SW NE SW (location) Sec 19 Twp 1 S, Rge 22 East West

1650 Ft North from Southeast Corner of Section
3630 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5302
Name Red Tiger Drilling
City/State Wichita, Kansas

Nearest lease or unit boundary line 330 feet.
County Norton

Lease Name Donovan Well# 1

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 118 feet

Lowest usable water formation Dakota

Depth to Bottom of usable water 1000 feet

Surface pipe by Alternate: 1 2

Surface pipe to be set 260 feet

Conductor pipe if any required 40 feet

Ground surface elevation 2442 feet MSL

This Authorization Expires 7-25-85

Approved By 1-25-85 RC

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 3700 feet
Projected Formation at TD Arbuckle
Expected Producing Formations Arbuckle

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

ite 1-24-85 Signature of Operator or Agent Greg Bechtol Title Sr. Engr. Tech

Form C-1 4/84

RECEIVED
STATE CORPORATION COMMISSION

FEB 25 1985

CONSERVATION DIVISION
Wichita, Kansas