

To: 6 031313  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-5  
API NUMBER 15- 039-20,478-20-00 *28R*

NE ME SE, SEC. 7, T 1 S, R 26 W/E  
2310 feet from S section line  
330 feet from E section line

Lease Name Powell Well # 1  
County Decatur *116.68*  
Well Total Depth 3590 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 206

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Co. License Number \_\_\_\_\_

Address Chase, Ks.

Company to plug at: Hour: AM Day: 5 Month: Jan Year: 19 90

Plugging proposal received from Mike Kelso

(company name) Kelso (phone) \_\_\_\_\_

were: 8 5/8" set at 206' w/145 sks cwc. 4 1/2" set at 3575' w/250 sks.

Perf 3361' - 3453'. O.H. 3575' - 87'. PBTD 3587'. Order sand and common cement.

Pull pipe. Order 225 sks 65/35 poz 10% gel 2% dicel, 500# hulls. Allied Cement Co.

LaRue Water Truck.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:45AM Day: 5 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT Sand bottom to 3525' w/4 sks common cement on sand w/

biler. Recovered 1630' of 4 1/2" casing. Wireline to anhy. Sq 8 5/8" casing

w/225 sks cement blend w/500# hulls mixed into max psi #. Close in psi #.

Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 26 1990  
26, 1990

CONSERVATION DIVISION  
Wichita, Kansas  
Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

Signed Carl Goodrow  
(TECHNICIAN)  
Carl Goodrow

INVOICED

DATE FEB 07 1990

INV. NO. 27356