

6 031094

5-18-88 15-039-20095-0001
NA

API NUMBER 15-

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE, SEC. 8, T 1 S, R 26 W/

4620 feet from S section line

1980 feet from E section line

Lease Name Bleeps Well # 2 SWD

County Decatur 116.06

Well Total Depth 3571 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 244

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Operator: A.L. Abercrombie Inc.
Name & Address: Route 1 Box 56
Great Bend, Ks. 67530

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing License Number 6050

Address Chase, Ks.

Company to plug at: Hour: AM Day: 18 Month: May Year: 19 88

Plugging proposal received from Ronnie

(company name) Kelso (phone)

were: 8 5/8" set at 244' w/200 sks cwc. 5 1/2" set at 3482' w/150 sks.

PBTD 3463'. Perf 3306' -10' Order sand and Common Cement. Pull pipe. Order 200 sks Cement Blend w/5 sks Hulls. Halliburton Cement Co. LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30AM Day: 18 Month: May Year: 19 88

ACTUAL PLUGGING REPORT Sand bottom to 3400' w/5 sks Common Cement on sand w/bailer.

3 shots 2500' - Anhy 1955'. Base of Dakota recovered 1040' of 5 1/2" casing. Squeezed 8 5/8" w/50 sks Cement followed w/150 sks cement w/5 sks Hulls mixed in last 100 sks to max Psi 500#. Close in Psi 500#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
7-6-88
JUL 6 1988

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
Please observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

DATE 7-7-88
INV. NO. 21191