



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

15-137-20060-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Forbes Csg. Pulling Co., Inc. has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Will P. Ash,

Complete Address: 360 Sutton Place, Wichita, Kansas.

Lease Name: Wyatt Well No. 1

Location: SW-SW SE Sec. 21 Twp. 1 Rge. (E)(W) 23

County: Norton Total Depth 3614' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

218'--8 5/8" Surface casing cement circulated.

3617'--4 1/2" Production casing cemented on bottom with 125 Sx.. Well plugged back to 3614'. Top perforations @ 3426'.

Push plug to 3400', sand back to 3375' and set 4 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 135 Sx. cement, staged.

Very truly yours,

A. L. Nichols
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
DEC 1 - 1970
CONSERVATION DIVISION
Wichita, Kansas