



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15-137-20032-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. M. H. Mayfield of Leben Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Mayfield guarantees payment of the plugging fee.

Operator's full Name: Tilco et al,

Complete Address: 200 Sutton Place, Wichita, Kansas.

Lease Name: Rhoades Well No. 1

Location: NE-NW-SE Sec. 35 Twp. 1 Rge. (E)(W) 24

County: Norton Total Depth 3631' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mayfield was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 850'.

Circulate hole with heavy mud. Pull DP to 1075' and displace 100 Sx. cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent